	ADSR 11-15.2: Providing and fixing 450mm dia circular shape mirror with plastic moulded frame of approved make and shade with 6mm thick hard board backing including cost of materials, labour complete as per specifications. (P.82/I.12.40 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Unit							
	Basic Rate		12				**12**	935.28	**11223.00**
	Add: Area Weightage 8%	866.00							
	Total	69.28							
		935.28							
	Providing 15cms x 10cms stoneware gully trap of approved quality and make fixing in CC 1:2:4 and plastering with CM 1:3 wherever necessary. (Rate includes cost of all materials, fixtures and lead). (P.88/I.12.112.2 PW, P & IWTD,SOUTH ZONE -SR 2016-17)	Each							
			30				**30**	291.60	**8748.00**
	Basic Rate:	270.00							
	Area Weightage 8%	21.60							
	Total	**291.60**							
	Providing and fixing 12.5cms x 7.5cms Cl Nahani trap of approved make conforming to PSI specifications and construction of Cistern in M-15 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot). (P.88/I.12.113.2 PW, P & IWTD,SOUTH ZONE -SR 2016-17)	Each							
			13				**13**	307.80	**4001.00**
	Basic Rate:	285.00							
	Area Weightage 8%	22.80							
	Total	**307.80**							
	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) - 25mm nominal CD pipes (P.86/I.13.86.3 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	M							
	Basic Rate		15	6.00			**90.00**	270.00	**24300.00**
	Add: Area Weightage 8%	250.00							
	Total	20.00							
		270.00							
	ADSR 13-6.2-2 : Providing and fixing in position brass stop cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. ADSR 13-6.2.2/13.3 (P.91/I.13.27 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Each							
	Basic Rate		25				**25**	172.80	**4320.00**
	Add: Area Weightage 8%	160.00							
	Total	12.80							
		172.80							

13-11.1: Providing and placing on terrace, polyethylene water storage tanks with manhole lid and lockable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications. (For 1000 litre capacity). Specification No. KBS 13.22 P.94/I.13.78 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Nos								
Basic Rate		8467.00	4				4	9144.36	36577.00
Add: Area Weightage 8%		677.36							
Total		9144.36							
12-8.1 : Constructing brick masonry inspection chamber 600x600mm and 450mm depth (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, CI cover withframe (light duty) 600x600mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete 1:2:4 mix 20mm nest downsize granite metal, foundation concrete 1:5:10 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications. (P.73/I.11.50.1 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Nos								
Basic Rate		8954.00	10				10	9670.32	96703.00
Add: Area Weightage 8%		716.32							
Total		9670.32							
15-8.9 : Providing and fixing to wall, ceiling and floor high density polyethylene pipes 6.00 kgf/sq.cm working pressure 140mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No. KBS 13.2.15.2 / 13.9 P.94/I.13.73.6 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	M								
For Sanitary Purpose			1	50.00			50.00	774.36	38718.00
Basic Rate		717.00							
Add: Area Weightage 8%		57.36							
Total		774.36							
providing and fixing polished granite sink of size 60cms of 23cm thick, the sink portion shall be 15cm depth of shapes oval/round/square over brick masonry in cement mortar 1:6 including cost and conveyance of all materials, labour for all items of work, HOM of equipment for all lead and lift, loading and unloading, transportion charges and all other incidential charges etc., complete as per specification and directions of the Engineer-in-charge and other work. (P.97/I.13.90 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Each								
Basic Rate		4844.00	2				2	5231.52	10463.00
Add: Area Weightage 8%		387.52							

	Total	5231.52							
159	Providing and fixing Stainless steel 304 grade for staircase railings, balconies, ramps with hand rail, 50mm dia 16 guage hollow pipe welded to vertical hollow 50mm dia pipe of 16 guage, stainless steel vertical pipe spaced at 1.20m regular intervals, and 5 Nos of 25mm dia. Stainless steel hollow horizontal pipe are welded to vertical 50mm dia hollow pipe. The entire assembly is fixed to staircase concrete by using expansion bolts by drilling concrete etc., complete including cost of materials, labour, HOM of machineries and electrical charges etc., complete as per specification. (P.43/I.7.38 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Sqm							
	For Staircase		2	6.00		1.00	**12**	6638.76	**79665.00**
	Basic Rate	6147.00							
	Addl Area Weightage 8%	491.76							
	Total	6638.76							
160	Providing and fixing 60x60cms M.S. inspection door with necessary M.S. frame made out of M.S. angle 50x50x6mm and M.S. shutters of 31.5mm or B.G.10 thick with hinges on top and locking arrangement, painting etc., complete (for RCC over head tank and G.L.S.R.) (P. No.23 I. No. 4.9) PHE SR. 2012-13	Each							
	For Sump		2				**2**	1927.13	**3854.00**
	Basic Rate	1871.00							
	Addl Area Weightage 3%	56.13							
	Total	1927.13							
161	KSHB 15-15.1: Providing and applying painting in two coats with plastic emulsion paint with primer of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. - with primer (P.117/I.15.51.2 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Sqm							
	GF		Qty Vide Item No 41				**1269.17**	97.20	**123363.00**
	Basic Rate	90.00							
	Addl Area Weightage 8%	7.20							
	Total	97.20							
	FF		Qty Vide Item No 41				**1294.87**	100.20	**129745.00**
	Basic Rate	90.00							
	Addl Area Weightage 8%	7.20							
	Add Lift Charges for Ist Floor (1 x 3.00)	3.00							
	Total	**100.20**							
162	KSHB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint with primer of approved brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. - with primer (P.118/I.15.53.2 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Sqm							
	GF		Qty Vide Item No 42				**580.84**	90.72	**52694.00**
	Basic Rate	84.00							
	Addl Area Weightage 8%	6.72							

	Total	90.72							
b	FF		Qty Vide Item No 42				**491.99**	93.72	**46109.00**
	Basic Rate	84.00							
	Add Area Weightage 8%	6.72							
	Add Lift Charges for Ist Floor (1 x 3.00)	3.00							
	Total	**93.72**							
(c)	KSRB 15-1 8.1 : Applying red lead ready mix priming coat over new steel or other metal surface including preparing the surface after throughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushes, fine steel wool, sand papers including cost of materials, labour, complete as per specifications. (P.121/I.15.73 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Sqm							
a	GF - CG	2.25	2	4.60		2.50	51.75		
	MD	2.25	1	1.20		2.10	5.67		
	D	2.25	7	1.00		2.10	33.08		
	D1	2.25	7	0.90		2.10	29.77		
	W	1.00	12	1.50		1.20	21.60		
	W1	1.00	1	1.20		1.20	1.44		
	V	1.00	8	0.90		0.60	4.32		
	V1	1.00	4	1.20		0.60	2.88		
	GW	1.00	1	2.60		1.50	3.90		
	GW1	1.00	1	4.60		1.50	6.90		
	Shops - RS	2.25	4	3.30		3.00	89.10		
	Basic Rate	29.00					**250.40**	31.32	**7843.00**
	Addl Area Weightage 8%	2.32							
	Total	31.32							
	FF - MD	2.25	2	1.20		2.10	11.34		
	D	2.25	8	1.00		2.10	37.80		
	D1	2.25	5	0.90		2.10	21.26		
	W	1.00	18	1.50		1.20	32.40		
	W1	1.00	1	1.20		1.20	1.44		
	V	1.00	8	0.90		0.60	4.32		
	V1	1.00	4	1.20		0.60	2.88		
	GW	1.00	1	2.60		1.50	3.90		
	GW1	1.00	1	4.60		1.50	6.90		
							122.24	34.32	**4195.00**
	Basic Rate	29.00							
	Addl Area Weightage 8%	2.32							
	Add Lift Charges for Ist Floor (1 x 3.00)	3.00							
	Total	**34.32**							
	KSRB 15-18.2: Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. (P.122/I.15.74 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Sqm							
	GF - CG	2.25	2	4.60		2.50	51.75		
	MD	2.25	1	1.20		2.10	5.67		
	D	2.25	7	1.00		2.10	33.08		
	D1	2.25	7	0.90		2.10	29.77		
	W	1.00	12	1.50		1.20	21.60		
	W1	1.00	1	1.20		1.20	1.44		
	V	1.00	8	0.90		0.60	4.32		
	V1	1.00	4	1.20		0.60	2.88		
	GW	1.00	1	2.60		1.50	3.90		
	GW1	1.00	1	4.60		1.50	6.90		
	Shops - RS	2.25	4	3.30		3.00	89.10		

						250.40	88.56	**22176.00**
Basic Rate	82.00							
Add Area Weightage 8%	6.56							
Total	88.56							
FF - MD	2.25	2	1.20		2.10	11.34		
D	2.25	8	1.00		2.10	37.80		
D1	2.25	5	0.90		2.10	21.26		
W	1.00	18	1.50		1.20	32.40		
W1	1.00	1	1.20		1.20	1.44		
V	1.00	8	0.90		0.60	4.32		
V1	1.00	4	1.20		0.60	2.88		
GW	1.00	1	2.60		1.50	3.90		
GW1	1.00	1	4.60		1.50	6.90		
						122.24	91.56	**11193.00**
Basic Rate	82.00							
Add Area Weightage 8%	6.56							
Add Lift Charges for Ist Floor (1 x 3.00)	3.00							
Total	**91.56**							
KSRB 8.6-7 : Providing and fixing on wall surface 4.0 kg / sq.cm H.D.P.E. rain down water pipes 90 mm outer dia. approved make and brand with necessary specials like shoes, bends and offsets fixed with iron clamps, wall plugs, screws, including cost of materials, labour, complete as per specifications. (P.47/I.8.18 PW, P & IWTD, SOUTH ZONE - SR 2016-17)	Mtr							
Rain water pipes		15	6.00			**90.00**	462.24	**41602.00**
Basic Rate	428.00							
Add Area Weightage 8%	34.24							
Total	462.24							
KSRB 10-3: Providing and laying integral cement based waterproofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc., consisting of following application. (a) Applying and grouting a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with proprietary water proofing compound conforming to S:2645 over the RCC slab after cleaning the surface before treatment. (b) Laying cement concrete using broken brick bats 25mm to 100mm size with 50 kg/c of cement mortar 1:5 admixed with proprietary water proofing compound conforming IS:2645 over 20mm thick layer of cement mortar 1:5 admixed with proprietary water proofing compound to required slope and treating similarly the adjoining walls upto 300mm height including rounding off junctions of walls and slabs.	Sqm							
(c) After two days of proper curing, applying a second coat of cement lurry admixed with proprietary water proofing compound (d) Finishing the surface with 20mm thick jointless cement mortar of mix 1:4 admixed with proprietary water proofing compound and finally finishing the surface with trowel and neat cement slurry and making of 300x300mm square. (e) The whole terrace so finished shall be flooded with water fora minimum period of two weeks for curing and for final test including cost of materials, labour complete as per specifications. (P.66/I.10.2 PW, P & IWTD, SOUTH ZONE -SR 2016-17)								
FF - Roof Top-WPc		1	20.00	8.90		178.00		
		1	3.00	3.60		10.80		

	Cabin- 03& 04		1	14.00	5.70		79.80		
	Waiting Lounge		1	13.00	6.80		88.40		
	Cabin- 01& 02		1	10.00	4.30		43.00		
	Gents &ladies Toilets		1	7.00	3.00		21.00		
			1	3.10	2.50		7.75		
	Deduction - Staircase and Lift Portion						**428.75**		
			1	6.00	4.60		27.60		
	Basic Rate	904.00					**401.15**	976.32	**391651.00**
	Add Area Weightage 8%	72.32							
	Total	976.32							
127	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification. (P.109/I.14.62 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Sqm							
	Out Side Portion -Front Portion								
	South Side		1	20.00	2.00		40.00		
	West Side		1	15.00	1.20		18.00		
			1	6.20	1.80		11.16		
			1	3.00	0.60		1.80		
			1	3.30	1.70		5.61		
	North Side		1	6.50	1.90		12.35		
			1	31.00	1.00		31.00		
	Basic Rate	1085.00	2	5.00	1.00		10.00		
	Add Area Weightage 8%	86.80					**129.92**	1171.80	**152240.00**
	Total	1171.80							
	For Electrical Works								
	Supplying and wiring adopting loop system in existing PVC Conduit/casing capping using copper PVC insulated multi strand 2x1.5 Sq mm copper wire with a 6 Amps flush type SP control switch shall be fixed on the existing plastic sheet piping box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block complete for each outlet. (P.5/I.2.1 PWD,ELE -SR 2014-15)	Point							
	Short point-up to 3 Mtrs from tapping point to out let via switch.		50				**50**	174.00	**8700.00**
	Medium point above 3 Mtrs up to 6 Mtrs from tapping point to out let via switch		50				**50**	245.00	**12250.00**
	Long point above 6 Mtrs up to 10 Mtrs from tapping point to out let via switch		50				**50**	363.00	**18150.00**
	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting base plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal / PVC box.(P.16/I.3.6.1 PWD,ELE -SR 2014-15)	No							
	One Module		200				**200**	109.00	**21800.00**

Supplying 6A flush/projected type socket and 6 amps flush/projected type SP switch either surface/flush mounting in a existing gang box or in a 4mm thick plastic sheet and fixing over a flush mounted wooden box and wiring using necessary capacity wires as required. 6 Amps 2 Way (P.15/I.3.1.1 PWD,ELE -SR 2014-15)	No							
		200				**200**	127.00	**25400.00**
Supplying and flush mounting powder coated metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall (P.16/I.3.5.6 PWD,ELE -SR 2014-15)	No							
16 Way		200				**200**	172.00	**34400.00**
Supplying 4mm thick plastic sheet with necessary nitches for fixing switches regulators etc., and fixing on existing wooden or metal box using N.F. screws. (P.17/I.3.10 PWD,ELE -SR 2014-15)	Sqcm							
		150000.00				**150000.00**	0.22	**33000.00**
Supplying heavy gauge PVC conduit pipe 20mm dia confirming to IS 2509 with suitable size bends, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall stone structure or rawl plugs in case of brick walls and cement plastering damaged portion using heavy gauge saddles at an interval of 700mm using NF screws.(P.2/I.1.1.1 PWD,ELE -SR 2014-15)	Rmtr							
		10	50.00			**500.00**	54.00	**27000.00**
Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipments on the meter board using 40mm dia 2.90 mm thick GI pipe 2.5 mtr long buried in a pit..... The pit should be filled with equal proportion of salt and charcoal 150 mm alround the pipe to complete depth. The connection from the pipe to the conduit etc, is to be established through GI wire of size as per IS1 specification 7.33 of IS 732 using 12 mm dia bolts, nuts, washers and checknuts etc, the pipe shall have 16 through holes of 122 mm dia.(P.55/I.7.1PWD,ELE -SR 2014-15)	Each							
		2				**2**	2727.00	**5454.00**
Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers etc., complete. 32 AMPS (P.45/I.6.7.2 PWD,ELE -SR 2014-15)	Each							
		50				**50**	180.00	**9000.00**
Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF,energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required. (P.47/I.6.16.1 PWD,ELE -SR 2014-15)	Each							
5-32 Amps		50				**50**	418.00	**20900.00**
Supply and fixing of bakelite D.P/Socket/switch with/without neon indicator over existing wood board or flush mounting in plastic plates/nitches. 16 Amps Combined switch and socket with indication (P.15/I.3.3.4PWD,ELE -SR 2014-15)	Each							
		50				**50**	194.00	**9700.00**

78	Supplying and fixing PBBC brass/Bakelite straight or slant batten holder and wiring, within 60W/230 Volts lamps. (P.20/I.4.2 PWD,ELE -SR 2014-15)	Nos							
			50				**50**	88.00	**4400.00**
79	Wiring for lighting / power circute using one of PVC insulated 1100v/grade multies and copper conductor single core cable in open or consealed system of wiring A Group materials 4.00 Sqmm materials P.6/I.2.5.4 PWD,ELE -SR 2014-15)	Rmtr							
			15	100.00			**1500.00**	42.10	**63150.00**
80	Wiring for lighting / power circute using one of PVC insulated 1100v/grade multies and copper conductor single core cable in open or consealed system of wiring A Group materials 2.50 Sqmm materials (P.6/I.2.5.3 PWD,ELE -SR 2014-15)	Rmtr							
			15	100.00			**1500.00**	29.20	**43800.00**
81	Fixing one exhaust fan after making a suitable nitch in the wall and finishing with cement mortar and colouring to match the existing wall or brackets, with bolts and nuts and a 5 amps, ceiling rose with sufficient length of 23 / 0.0076 inch PVC insulated twin core wire of approved make with wire mesh and wooden frame. (P.109/I.17.11 PWD,ELE -SR 2014-15)	Nos							
			15				**15**	680.00	**10200.00**
82	Supplying exhaust fan of 1440 RPM of 300mm (12") size with bracket blades complete for light duty suitable to operate on 230V 50Hz, AC Supply. (P.78/I.9.1 PWD,ELE -SR 2014-15)	Nos							
			15				**15**	1700.00	**25500.00**
83	Supply of 2'x2' LED recessed luminaire with ...Watts system wattage. Housing shall be with pressure die cast aluminum alloy with corrosion proof resistant polyester power coated. Driver operates with voltage range from 100V to 270V 50/60 Hz with short circuit, overload & mis-wiring protection. Lumen Maintenance of 70% at 50000 Hrs. Injection moulded poly carbonate diffuser for better mechanical stability, light transmission & avoid pot hole effect. Junction temperature shall be < 70 degree Celsius. Driver is on constant current driver @ 0.06A with PF > 0.92 with line voltage @ 220-240V @ 50/60Hz, driver efficiency > 85% & THD<15%. LED Efficiency > 130 lm/W at 1W & Fixture Efficiency >75lm/w with CRI > 75 with injection moulded Polycarbonate lens with < 80mm depth. 5 years Warranty against any manufacturing defect working under standard electrical condition.(P.26/I.4.33.3 PWD,ELE -SR 2014-15)	Each							
a	**GF -LED modular down light 1'x1'-36 watts**		30				**30**	7006.00	**210180.00**
b	**FF-LED modular down light 2'x2'-55 watts**		20				**20**	9273.00	**185460.00**
84	Supply and fixing polished wood board made of not less than 15mm thick plank on both sides of not more than 2 pieces and fixing the same to the wall using tapered inwerted wooden plugs screws. (P.44/I.17.8 PWD,ELE -SR 2014-15)	Each							
a	12"x12"x2"		20				**20**	153.00	**3060.00**
b	15"x12"x2"		10				**10**	177.00	**1770.00**
c	20"x20"x2.5"		10				**10**	302.00	**3020.00**

85	Supplying and fixing PVC/metal conduit Deep junction box (P.2/I.1.5 PWD,ELE -SR 2014-15)	Each							
	32mm deep junction box		100				**100**	65.00	**6500.00**
86	Extra for Groove cutting in brick wall/CC floor to the suitable depth for concealing of Conduit/GI pipe and plastering, finishing upto wall surface complete. (P.3/I.1.7 PWD,ELE -SR 2014-15)	Mtr							
	upto 50mm conduit in brick wall		10	15.00			**150.00**	21.00	**3150.00**
87	Supplying and fixing regular MCCB distribution Panel confirming to IS 8828, on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing of suitable type capacity MCCB's as an incomer for 3 phase Double door with necessary bus bar completely wired to use on 440Volts 3phase 4 wire powder coated painting etc., complete with a provision for fixing of single/three phase suitable capacity MCCB/MCB's as outgoings confirming to IS8828. (P.46/I.6.2 PWD,ELE -SR 2014-15)	Each							
	12Way		6				**6**	11854.00	**71124.00**
88	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete.(As per Civil SR KSRB I-2, P-7) (P.61/I.7.9 PWD,ELE -SR 2014-15)	Mtr							
	In soil (hard)		1	50.00			**50.00**	106.00	**5300.00**
89	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV. (P.62/I.7.12 PWD,ELE -SR 2014-15)	Mtr							
	40mm		1	50.00			**50.00**	345.00	**17250.00**
90	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A. (P.55/I.7.4 PWD,ELE -SR 2014-15)	Mtr							
	4 core 16 sqmm		1	50.00			**50.00**	140.40	**7020.00**
91	Supplying Capacitor type ceiling fan complete with down rod blades shackle canopies etc for operation on 230volts 50cycles single phase AC supply confirming to ISS-374-1979 and with double ball bearing system 56" Sweep (1400mm) (P.78/I.9.3.2.1 PWD ELE - SR 2014-15)	Each				s			
	Regular Model-GF		15				15		
	FF		15				15		
							30	2418.00	**72540.00**

92	Fixing a ceiling fan of all capacities and all types to the existing S hook with fan regulator to the existing board together with supplying and fixing a 5 ampers ceiling rose, necessary length of 23/0.0076 inch PVC insulated twin twisted copper wire and wiring completely. (P.109/I.17.9 PWD,ELE -SR 2014-15)	Nos							
	Regular Model-GF		15				15		
	FF		15				15		
							30	237.00	**7110.00**
93	Supplying and Installing 1.00HP / 75 KW 10Stage Submersible Single Phase Motor (P.XXXXIV / I.1 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Set							
			1				**1**	12600.00	**12600.00**
94	Meter and Panel Board: Supply and delivery of meter and panel board unit one number of MS box of size 300 x 120mm size fabricated out of 2mm thick sheet metal with sealable door arrangement for mounting the CTS(if any) cutouts 3 phase dia 4 wire energy meter and cable box complete. A transparent glass piece should be provided where the energy meter reading could be read. b. Panel Board (1.00HP) One number of cubicle type of control panel board to operate on 50c/400/400v	Each							
			1				**1**	1370.00	**1370.00**
								SUB - TOTAL AMOUNT RS.	**17670776.00**
95								G.S.T Charges (12%)	**2120493.12**
96								PMC and Third Party Inspection Charges (1%)	**176707.76**
97								BESCOM DEPOSIT LS	**20000.00**
98								Miscellaneous,TenderPremium Charges and Unforeseen Charges LS	**12023.12**
								TOTAL AMOUNT RS.	**20000000.00**

(Rupees Two Crore Only)

CERTIFICATE :

1 The work spot has been inspected and found to be necessary.
2 The work spot comes under BBMP Limits.
3 The provisions made in the estimate are necessary and minimum.
4 The estimate is based on PWD ELE SR 2014-15 & PW, P & IWTD,SOUTH ZONE - SR 2016-17.

Assistant Engineer
Ward No.07

Assistant Executive Engineer
Kodigehalli Sub Division
BBMP Bangalore

Executive Engineer
Byatarayanapura Division
BBMP Bangalore

	Fixing a ceiling fan of all capacities and all types to the existing S hook with fan regulator to the existing board together with supplying and fixing a 5 ampers ceiling rose, necessary length of 23/0.0076 inch PVC insulated twin twisted copper wire and wiring completely. (P.109/I.17.9 PWD,ELE -SR 2014-15)	Nos							
	Regular Model-GF		15				15		
	GF		15				15		
							30	237.00	7110.00
	Supplying and installing 1.00HP / 75 KW 10Stage Submersible Single Phase Motor (P.XXXXIV / I.1 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Set							
			1				1	12600.00	12600.00
	Meter and Panel Board: Supply and delivery of meter and panel board unit one number of MS box of size 300 x 120mm size fabricated out of 2mm thick sheet metal with suitable door arrangement for mounting the CTS(if any) contacts 3 phase dia 4 wire energy meter and cable box complete. A transparent glass piece should be provided where the energy meter reading could be read. b. Panel Board (1.00HP) One number of cubicle type of control panel board to operate on 50c/400/400v	Each							
			1				1	1370.00	1370.00
								SUB - TOTAL AMOUNT RS.	17670776.00
								G.S.T Charges (12%)	2120493.12
								PMC and Third Party Inspection Charges (1%)	176707.76
								BESCOM DEPOSIT LS	20000.00
								Miscellaneous,TenderPremium Charges and Unforeseen Charges LS	12023.12
								TOTAL AMOUNT RS.	20000000.00

(Rupees Two Crore Only)

CERTIFICATE :

1 The work spot has been inspected and found to be necessary.
2 The work spot comes under BBMP Limits.
3 The provisions made in the estimate are necessary and minimum.
4 The estimate is based on PWD ELE SR 2014-15 & PW, P & IWTD,SOUTH ZONE - SR 2016-17.

Assistant Engineer
Ward No.07

Assistant Executive Engineer
Kodigehalli Sub Division
BBMP Bangalore

Executive Engineer
Byatarayanapura Division
BBMP Bangalore

Administrative Approval
Accorded For Rs. 2 Crores
Head of A/C 3242
CER NO : 18 Dt: 25/07/2019

E.E. (Project)

Technical Sanction
Accorded For Rs. 2 Crores
Head of A/C 3242
CER NO : 183 Dt: 05/01/2019

TA : CE (YNK)